



Government of India
Ministry of Environment, Forest and Climate Change
(Issued by the State Environment Impact Assessment
Authority(SEIAA), Maharashtra)

To,

The Proprietor
 GHANSHAMDAS SUKHWANI
 32, Sukhwani Chambers, Pimpri Pune - 411018 -411018

Subject: Grant of Environmental Clearance (EC) to the proposed Project Activity under the provision of EIA Notification 2006-regarding

Sir/Madam,

This is in reference to your application for Environmental Clearance (EC) in respect of project submitted to the SEIAA vide proposal number SIA/MH/MIS/260397/2022 dated 07 Mar 2022. The particulars of the environmental clearance granted to the project are as below.

1. EC Identification No.	EC22B038MH146158
2. File No.	SIA/MH/MIS/260397/2022
3. Project Type	Expansion
4. Category	B2
5. Project/Activity including Schedule No.	8(a) Building and Construction projects
6. Name of Project	Expansion of Residential & commercial project - SUKHWANI SEPIA at S. no. 96/1,97/1/1, 97/2 Village-Tathwade, Tehsil- Mulshi, Pune by M/s. SUKHWANI CONSTRUCTIONS
7. Name of Company/Organization	GHANSHAMDAS SUKHWANI
8. Location of Project	Maharashtra
9. TOR Date	N/A

The project details along with terms and conditions are appended herewith from page no 2 onwards.

Date: 16/07/2022

(e-signed)
Manisha Patankar Mhaikar
 Member Secretary
 SEIAA - (Maharashtra)

Note: A valid environmental clearance shall be one that has EC identification number & E-Sign generated from PARIVESH. Please quote identification number in all future correspondence.

This is a computer generated cover page.



STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

No. SIA/MH/MIS/260397/2022
Environment & Climate
Change Department
Room No. 217, 2nd Floor,
Mantralaya, Mumbai- 400032.

To
M/s. Sukhwani Constructions,
S. no. 96/1,97/1/1, 97/2 Village-Tathwade,
Tehsil- Mulshi, Pune.

Subject : Environment Clearance for Expansion of Residential & commercial project - SUKHWANI SEPIA at S. no. 96/1,97/1/1, 97/2 Village-Tathwade, Tehsil- Mulshi, Pune by M/s. Sukhwani Constructions

Reference : Application no. SIA/MH/MIS/260397/2022

This has reference to your communication on the above mentioned subject. The proposal was considered by the SEAC-3 in its 143rd meeting under screening category 8 (a) B2 as per EIA Notification, 2006 and recommend to SEIAA. Proposal then considered in 245th (Day-1) meeting of State Level Environment Impact Assessment Authority (SEIAA).

2. **Brief Information of the project submitted by you is as below:-**

1	Proposal Number	SIA/MH/MIS/260397/202	
2	Name of Project	Expansion of Residential cum commercial project – SUKHWANI SEPIA at S. no. 96/1,97/1/1, 97/2, Village-Tathwade, Tehsil- Mulshi, District - Pune, State - Maharashtra by M/s. SUKHWANI CONSTRUCTIONS	
3	Project category	8 (a), B2	
4	Type of Institution	Private	
5	Project Proponent	Name	M/s. Sukhwani Constructions
		Regd. Office address	32, Sukhwani Chambers, Pimpri, Pune - 411018
		Contact number	020 - 27421454
		e-mail	sukhwanisepia77@gmail.com
6	Consultant	Sneha Hi-Tech Products NABET Accredited Certificate No. NABET/EIA/1619/IA0028 dated 13.07.2017 valid till 06.06.2022	
7	Applied for	Expansion	
8	Details of previous EC	EC vide letter no. SEAC-2212/CR-705/TC-2 on 03.12.2016	
9	Location of the project	S. no. 96/1,97/1/1, 97/2, Village-Tathwade, Tehsil- Mulshi, District - Pune, State - Maharashtra	
10	Latitude and Longitude	Latitude: 18°36'44.28"N , Longitude: 73°44'37.54"E	
11	Total Plot Area (m2)	31,598.95	
12	Deductions (m2)	1,125.67	
13	Net Plot area (m2)	28,949.62	

14	Proposed FSI area (m2)	95,968.88					
15	Proposed non-FSI area (m2)	46,746.75					
16	Proposed TBUA (m2)	1,42,715.63					
17	TBUA (m2) approved by Planning Authority till date	Sanction No. B.P/Env/Tathawade/08/2021 dtd 02.07.2021					
18	Ground coverage (m2) & %	6845.57 sq.m (23.64%)					
19	Total Project Cost (Rs.)	Rs. 204 Cr.					
20	CER as per MoEF & CC circular dated 01/05/2018	NA, per Memorandum 22-65/2017-IA-III dated 25th February 2021					
21	Det ails of Building Configuration: <Please use following legends: Floor = F , Parking = Pk, Podium = Po, Stilt =St, Lower Ground = LG, Upper Ground = UG, Basement = B, Shops = Sh>						Reason for Modification /Change
	Previous EC / Existing Building		Proposed Configuration				
	Building name	Configuration	Height (m)	Building name	Configuration	Height (m)	
	Building A1	P+12 floors	38.76	Building A1	P+12 floors	38.76	No Change
	Building A2	P+12 floors	38.76	Building A2	2B+P+22 floors	68.46	Change in planning
	Building B1	P+12 floors	38.76	Building B1	P+12 floors	38.76	No Change
	Building B2	P+12 floors	38.76	Building B2	P+12 floors	38.76	
	Building B3	P+12 floors	38.76	Building B3	P+12 floors	38.76	
	Building B4	P+12 floors	38.76	Building B4	2B+P+22 floors	68.46	Change in planning
	Building B5	P+12 floors	38.76	Building C2	2B+P+22 floors	68.46	
	Building C1	P+12 floors	38.76	Building C1	P+12 floors	38.76	No Change
	Building C2	P+12 floors	38.76	Building C3	2B + P+22 floors	68.46	Change in planning
	Commercial building (Amenity Space)	-	-	Building D	2B + P+22 floors	68.50	
				Building E	2B + Gr + 12 floors	42.09	
				Building F	2B + P + 22 floors	68.50	
	Club House	G+1 floor	7.5	Club House	G+1 floor	7.5	No Change
				Covered Parking	G floor	3.12	-
23	Total number of tenements		Resiential:1260 nos. Commercial: 5286.46 sq.m Users: 6550 nos.				

24	Water Budget	Dry Season (CMD)		Wet Season (CMD)	
		Fresh Water	516 KLD	Fresh Water	516 KLD
		Recycled (Flushing)	267 KLD	Recycled (Flushing)	267 KLD
		Recycled (Gardening)	24 KLD	Recycled (Gardening)	0 KLD
		Swimming Pool	--	Swimming Pool	--
		Total	807 KLD	Total	783 KLD
		Waste water generation	705 KLD	Waste water generation	705 KLD
25	Water Storage Capacity for Firefighting / UGT (m3)	Tank		Capacity (cum)	
		Raw water tank		25	
		Utility water tank		Residential – 740 Commercial - 45	
		Drinking water tank		55	
		Fire tank		700	
		Treated water tank		285	
26	Source of water	PCMC/treated water			
27	Rainwater Harvesting (RWH)	Level of the Ground water table:		Pre monsoon: 14.67 m.to 21.67 m. BG Post monsoon: 10.50 m.to 15.17 m. BGL.	
		Size and no of RWH tank(s) and Quantity:		Nil	
		Quantity and size of recharge pits:		14 nos. 1.5m X 2.5 m X 2 m & 1.5m X 2.5 m X 1.75 m	
		Details of UGT tanks if any:		--	
28	Sew age and Wastewater	Sewage generation in CMD:		705 KLD	
		STP technology:		MBBR	
		Capacity of STP (CMD):		340 KLD & 375 KLD	
29	Solid Waste Management during Construction Phase	Type	Quantity (kg/d)	Treatment / disposal	
		Dry waste:	8.75		
		Wet waste:	3.75		

		Total waste	12.5	Utilized on site at maximum extent. Rest handed over to local body
30	Solid Waste Management during Operation Phase	Type	Quantity (kg/d)	Treatment / disposal
		Dry waste:	1254 kg/day	Handed over to Authorized Agency
		Wet waste:	1740 kg/day	Treated in OWC
		Hazardous waste:	Negligible	
		Biomedical waste	biomedical waste like Mask, Gloves, Face shields etc. (required for Pandemic situation)	Shall be segregated at designated place near OWC and shall be given to authorized vendor for management.
		E-Waste	19.49 kg/day	Shall be handed over to Authorized recycler for further handling & disposal purpose.
		STP Sludge (dry)	107 kg/year	Used as manure for gardening
31	Green Belt Development	Total RG area (m2):	On ground: 2,432.14sq.m Raised: 615.28 sq.m Total: 3,047.42 sq.m	
		Existing trees on plot:	202 nos.	
		Number of trees to be planted:	231 nos.	
		Number of trees to be cut:	9 nos.	
		Number of trees to be transplanted:	62 nos.	
32	Power requirement:	Source of power supply:	MSEB	
		During Construction Phase (Demand Load):	80 KW	
		During Operation phase (Connected load):	6437 KW	
		During Operation phase (Demand load):	2980 KW	
		Transformer:	5 x 630 kVA & 1 x 315 kVA	
		DG set:	2 X 320 kVA	

		Fuel used:		HSD		
33	Details of Energy saving	Total energy savings: 21.75 %				
34	Environmental Management plan budget during Construction phase	Type	Details			Cost
		Capital	Site Barricading, Personal Protective Equipment, Site Sanitation- Mobile toilets & Debris Management			0.78
		O&M	Water for Dust Suppression			0.14
			Site Sanitation, Disinfection & Safety			3.02
			Environmental Monitoring			2.0
			Health Check up			0.2
			Environment Management Cell			8.4
Total			14.28			
35	Environmental Management plan Budget during Operation phase	Component	Details	Capital (Rs.)	O&M (Rs./Y)	
		Sewage treatment	STP Operation and its maintenance	182.00	33	
		RWH & Storm water	Recharging existing ground water table,SWD - Connection to external line	17.5	0.7	
		Solid Waste	Collection Segregation and management of MSW	45.25	9.21	
		Hazardous waste	NA	-	-	
		E-waste	Collection Segregation and hand over to authorized vendors	Included in Solid waste		
		Green belt development	Plantation of new trees and maintenance of existing trees	62.27	12.45	

		Energy saving	Energy saving measures	191.05	3.82
		Environmental Monitoring	To monitor sustainability of Environmental Infrastructure	--	3.00
		Environment Management Cell	--	-	6.48
		Disaster Management	Emergency preparedness plan to develop and implement on site	101.45	25
		Total		599.97	93.66
36	Traffic Management	Type	Required as per DCR	Actual Provided	Area per parking (m2)
		4-Wheeler	585	613	38-39
		2-Wheeler	3051	3055	-
		Bicycles	518	518	-
37	Details of Court cases/litigations w.r.t. the project and project location if any.	No			

3. Proposal is an expansion of existing construction project. Project had received earlier EC vide letter No. SEAC-2212/CR-705/TC-2 on 03.12.2016 for Plot area 31,598.95 m², FSI area 35,331.66 m² Non-FSI- 33,177.31 m² & Total BUA- 68508.97m². (Earlier EC restricted to 62,558.97 m²). Proposal has been considered by SEIAA in its 245th (Day-1) meeting and decided to accord Environment Clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implantation of following terms and conditions-

Specific Conditions:

A. SEAC Conditions-

1. PP to submit the undertaking regarding they are restricting the project for total built up area 149500 Sq.mt and they will not utilised the remaining FSI in future also.
2. PP to provide minimum 30% of total parking arrangement with electric charging facility by providing charging points at suitable places.
3. PP to ensure that, the water proposed to use for construction phase should not be drinking water. They can use recycled water or tanker water for proposed construction.

4. It is noted that, the project will have the potable water through tankers; PP to add this information in his all documents like RERA, Advertisement of the project, agreement etc. Also PP to submit the water tanker agreement. Local body to ensure that, No Occupation Certificate should be issued unless project have sustainable water supply.
5. PP to submit Certified Compliance report from Regional Office MoEFCC Nagpur.

B. SEIAA Conditions-

1. PP to keep open space unpaved so as to ensure permeability of water. However, whenever paving is deemed necessary, PP to provide grass pavers of suitable types & strength to increase the water permeable area as well as to allow effective fire tender movement.
2. PP to achieve at least 5% of total energy requirement from solar/other renewable sources.
3. PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA.III dt.04.01.2019.
4. SEIAA after deliberation decided to grant EC for – FSI- 95,968.88 m², Non-FSI- 46,746.75 m² & Total BUA- 142715.63 m². (Plan approval- B.P./Env/Thathwade/08/2021 dated 02.07.2021).

General Conditions:

a) Construction Phase :-

- I. The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. Disposal of muck, Construction spoils, including bituminous material during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in the approved sites with the approval of competent authority.
- III. Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- IV. Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
- V. Arrangement shall be made that waste water and storm water do not get mixed.
- VI. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices.
- VII. The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
- VIII. Permission to draw ground water for construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
- IX. Fixtures for showers, toilet flushing and drinking should be of low flow either by use

- of aerators or pressure reducing devices or sensor based control.
- X. The Energy Conservation Building code shall be strictly adhered to.
 - XI. All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
 - XII. Additional soil for levelling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
 - XIII. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
 - XIV. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
 - XV. The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
 - XVI. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
 - XVII. Vehicles hired for transportation of Raw material shall strictly comply the emission norms prescribed by Ministry of Road Transport & Highways Department. The vehicle shall be adequately covered to avoid spillage/leakages.
 - XVIII. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
 - XIX. Diesel power generating sets proposed as source of backup power for elevators and common area illumination during construction phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel is preferred. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
 - XX. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings by a separate environment cell /designated person.

B) Operation phase:-

- I. a) The solid waste generated should be properly collected and segregated. b) Wet waste should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. c) Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.

- II. E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
- III. a) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Treated effluent emanating from STP shall be recycled/ reused to the maximum extent possible. Treatment of 100% grey water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP. b) PP to give 100 % treatment to sewage /Liquid waste and explore the possibility to recycle at least 50 % of water, Local authority should ensure this.
- IV. Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement.
- V. The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
- VI. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- VII. PP to provide adequate electric charging points for electric vehicles (EVs).
- VIII. Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
- IX. A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
- X. Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes.
- XI. The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at parivesh.nic.in
- XII. Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1st June & 1st December of each calendar year.
- XIII. A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on

the website of the Company by the proponent.


- XIV. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO₂, NO_x (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.

C) General EC Conditions:-

- I. PP has to strictly abide by the conditions stipulated by SEAC & SEIAA.
- II. If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
- III. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
- IV. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
- V. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
- VI. No further Expansion or modifications, other than mentioned in the EIA Notification, 2006 and its amendments, shall be carried out without prior approval of the SEIAA. In case of deviations or alterations in the project proposal from those submitted to SEIAA for clearance, a fresh reference shall be made to the SEIAA as applicable to assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.
- VII. This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.

4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.

5. This Environment Clearance is issued purely from an environment point of view without prejudice to any court cases and all other applicable permissions/ NOCs shall be obtained before starting proposed work at site.
6. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.
7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, amended from time to time.
8. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.
9. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1st Floor, D-Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.


Manisha Patankar-Manankar
(Member Secretary, SEIAA)

Copy to:

1. Chairman, SEIAA, Mumbai.
2. Secretary, MoEF & CC, IA- Division MOEF & CC
3. Member Secretary, Maharashtra Pollution Control Board, Mumbai.
4. Regional Office MoEF & CC, Nagpur
5. District Collector, Pune.
6. Commissioner, Pimpri Chinchwad Municipal Corporation
7. Regional Officer, Maharashtra Pollution Control Board, Pune .

